

LAMPIRAN

AHSP PT TIGAMAS MITRA SELARAS

A. 4.4.1.8 Pemasangan 1m2 dinding bata merah (5x11x22) cm tebal ½ batu campuran 1SP : 3PP						
No	Uraian	Kode	Satuan	Koefisien	Harga Satuan (Rp)	Jumlah Harga (Rp)
A	TENAGA					
1	Pekerja	L.01	OH	0,300		-
2	Tukang Batu	L.02	OH	0,100		-
3	Kepala Tukang	L.03	OH	0,010		-
4	Mandor	L.04	OH	0,015		-
B	BAHAN					
1	Batu bata		Bh	70,000		-
2	Semen PC 50 kg		Kg	14,370		-
3	Pasir Pasang		m3	0,040		-
C	PERALATAN					
D	Jumlah (A+B+C)					-
E	Overhead & Profit (Contoh 15%)			10% x D		-
F	Harga Satuan Pekerjaan (D+E)					-

Pemasangan 1 m ² dinding bataco campuran 1SP :4PP						
No	Uraian	Kode	Satuan	Koefisien	Harga Satuan (Rp)	Jumlah Harga (Rp)
A	TENAGA					
1	Pekerja	L.01	OH	0,120		-
2	Tukang Batu	L.02	OH	0,120		-
3	Kepala Tukang	L.03	OH	0,012		-
4	Mandor	L.04	OH	0,002		-
JUMLAH TENAGA KERJA						
B	BAHAN					
1	Bataco		bh	13,000		-
2	Semen PC 50 kg		Kg	5,833		-
3	Pasir Pasang		m3	0,013		-
JUMLAH HARGA BAHAN						-
C	PERALATAN		%	0,100	-	-
JUMLAH HARGA ALAT						-
D	Jumlah (A+B+C)					-
E	Overhead & Profit			10% x D		-
F	Harga Satuan Pekerjaan (D+E)					-

**DAFTAR HARGA SATUAN DASAR TENAGA KERJA DAN MATERIAL PT
TIGAMAS MITRA SELARAS**

NO	JENIS PEKERJAAN	SATUAN	HARGA (Rp)
I.	UPAH TENAGA KERJA		
1	Pekerja	Org / hr	80.000,00
2	Kepala Tukang Batu	Org / hr	105.000,00
3	Tukang Batu	Org / hr	95.000,00
4	Kepala Tukang Kayu	Org / hr	105.000,00
5	Tukang Kayu	Org / hr	95.000,00
6	Kepala Tukang Besi	Org / hr	105.000,00
7	Tukang Besi	Org / hr	95.000,00
8	Kepala Tukang Cat	Org / hr	105.000,00
9	Tukang Cat	Org / hr	95.000,00
10	Mandor	Org / hr	105.000,00
11	Tukang Pipa	org/hr	95.000,00
12	Pembantu Tukang Listrik	org/hr	95.000,00
13	Tukang Listrik	org/hr	95.000,00
14	Tukang Las	org/hr	95.000,00
15	Tukang Pompa	org/hr	95.000,00
16	Kepala tukang	org/hr	105.000,00
II.	BAHAN		
A.	BAHAN PASIR		
1	Pasir Urug / Tanah katel.	M3	160.000,00
2	Pasir Pasang	M3	225.000,00
3	Pasir Cor / Beton	M3	330.000,00
4	Tanah Urug	M3	114.500,00
5	Sirtu	M3	159.400,00

B.	BAHAN BATU		
1	Koral Beton 2/3	M3	145.000,00
2	Batu bata	Bh	750,00
3	Bataco	Bh	2.750,00
4	Bata Ringan 7,5 x 20 x 60 cm	Bh	8.250,00
5	Batu Kali 5/7	m ³	275.000,00
6	Kerikil 2/3	m ³	275.000,00
7	Roster 20 x 40	bh	20.000,00
8	Roster 20 x 20	bh	12.500,00
9	makadam	m ³	185.000,00
10	batu Andesit Bintik	M2	150.000,00
C.	BAHAN SEMEN, BETON		
1	Semen PC 50 kg	zak	58.000,00
2	Semen warna pengisi nat	1Kg	14.500,00
3	Semen Thinbed unt. acian	zak	65.000,00
4	Semen Skimcoat		6.000,00
5	Perekat Bata Ringan (Mortar MU - 380)	zak	85.000,00
6	Plesteran Mortar (MU - 200)	kg	3.500,00
7	Acian Motar (MU - 200)	kg	3.500,00
8	Air	Ltr	20,00
9	Beton Ready Mixed K-275	M3	925.000,00
10	Beton Ready Mixed K-300	M3	975.000,00
11	Tiang Pancang Beton 25 x 25 cm	m'	215.000,00